



# QUOTATION

**LARKIN INDUSTRIES, INC.**

114 David Green Road    Toll: 800-322-4036  
Birmingham, AL 35244    Fax: 205-987-0583

Quote Date: 00/00/0000  
Quote #.....: L-00000

**TO:      Company Name**  
**ATTN:   Contact Name**  
**PH:      xxx-xxx-xxxx**  
**FAX:      xxx-xxx-xxxx**

**JOB NAME: Sample Job**

**FROM: Larkin Sales Team**

QUANTITY    DESCRIPTION (Hood Size LxWxH)

1	<b>HOOD 1</b> <b>14' 3" x 48" x 24" Model: EO-FPSP</b> (EXHAUST ONLY-FRONT PERFORATED SUPPLY PLENUM ) WALL STYLE - 430 STAINLESS STEEL - WHERE EXPOSED WEIGHT: 721lbs 600 Degree ETL Label	\$ 0,000.00
4	Prewired Incandescent Light(s)	
2	14X14 Exhaust Collar(s) For Top Loose	
2	24X10 Supply Collar W/O Damper Loose	
1	183"X12" FPSP (Front Perforated Supply Plenum)	
1	3" Back Stand-Off Mounted (Stand-Off Adds to Width of Hood)	
1	15" S/S Ceiling Skirt	\$ 000.00
1	183X78 S/S Back Wall Splash Panel	\$ 000.00
1	*Hood Mounted Ansul R-102 Wet System RH-END (Fire Cabinet Adds 12" to Length of Hood)	\$ 0,000.00
1	Including up to 2" Mechanical Gas Valve	
1	Automatic Fan Controller per IMC 507.2.1.1 For 1 Stand Alone Hood 2 Contactor Package With 3 Switch Panel, 2 Switches and 1 Dial WALL MOUNT CFM REQUIREMENT: EXHAUST: 4290 CFMS @ .500 S.P. NOTE.....: S.P. Calculations Include Hood, Filters, and up to 8' of Straight Exhaust Duct. SUPPLY: 3432 CFMS @ .125 S.P. NOTE.....: S.P. Calculations Include Hood and up to 20' of Straight Supply Duct.	\$ 000.00
1	<b>UL-762 EXHAUST FAN - For HOOD: 1</b> <b>Model: XRUB-180-15</b> 1 1/2 HP 230 V 1 PH 10.00 AMPS <b>Exhaust Air Volume:</b> 4290 CFM @ 0.875SP      Weight: 126lbs 29X29 Flat Roof Curb	\$ 0,000.00
1	<b>DIRECT FIRED HEATED PACKAGE - For HOOD: 1</b> <b>Model: XDGK-112-20</b> 2 HP 230 V 1 PH 12.00 AMPS <b>Supply Air Volume:</b> 3432 CFM @ 0.125SP      Weight: 513lbs INCLUDES: ETL/IRI LISTING, FILTERED INLET HOOD WITH 2" ALUMINUM CLEANABLE FILTERS, DISCONNECT SWITCH, SUPPLY FAN STARTER WITH OVERLOAD PROTECTION, INSULATED HOUSING, ALUMINUM BURNER WITH STAINLESS STEEL MIXING PLATES, MAXITROL ELECTRONIC MODULATION CONTROL SYSTEM, INLET AIR SENSOR, A/C INTERLOCK RELAY AND GALVANIZED UNPAINTED CONSTRUCTION. NOTICE: UNIT IS SET UP FOR NATURAL GAS. IF OTHERWISE, PLEASE NOTIFY. UNITS HAVE A LEAD TIME OF 2-3 WEEKS. Natural Gas Down Discharge 27.5X27.5 Flat Roof Curb	\$ 0,000.00

# QUOTATION

JOB NAME: **Sample Job**

Date....: 00/00/0000

Quote #: **L-00000**

QUANTITY DESCRIPTION

1	<b>HOOD 2</b> <b>3' 6" x 42" x 24" Model: CH1</b> (STANDARD CONDENSATE HOOD ) WALL STYLE - 100% STAINLESS STEEL WEIGHT: 158lbs No ETL Label	<b>\$ 000.00</b>
1	11X11 Exhaust Collar(s) For Top Loose CFM REQUIREMENT: EXHAUST: 615 CFMS @ .250 S.P. NOTE.....: S.P. Calculations Include Hood, Filters, and up to 8' of Straight Exhaust Duct. SUPPLY: 492 CFMS @ .125 S.P. NOTE.....: S.P. Calculations Include Hood and up to 20' of Straight Supply Duct.	
1	<b>DIRECT DRIVE EXHAUST FAN</b> - For HOOD: 2 <b>Model: XRED-095-D</b> 1/8 HP 115 V 1 PH <b>Exhaust Air Volume:</b> 615 CFM @ 0.250SP Weight: 26lbs	<b>\$ 000.00</b>
1	16X16 Flat Roof Curb	

**EACH HOOD INCLUDES ALUMINUM FILTERS (UNLESS OTHERWISE NOTED),  
GREASE CUP, GREASE TRAY, HANGING BRACKETS (NO HANGING  
HARDWARE), NSF LABEL**

**SUB-TOTAL: \$ 00,000.00****TAX: \$ 0,000.00****THE ABOVE ITEMS INCLUDE FREIGHT****TOTAL: \$ 00,000.00**

---

## **QUOTATION FOR ADDITIONAL OPTIONS** (Add to above total if required)

1	Grease Trough for Exhaust Fan	<b>\$ 00.00</b>
1	Hinged Base Kit for Exhaust Fan	<b>\$ 00.00</b>
	Adder for Sloped Curb (per Curb)	<b>\$ 00.00</b>

**(Tax not included in Additional Options prices)**

## **FEATURED ACCESSORIES**

PYROSCAT DUCT WRAP XL- 300"X24"X1.5" 1 Roll  
UL Listed Flexible Insulating Blanket 0 clearance

LARKIN Offers a Complete Line of Duct Wrap Accessories.  
Please Call For Per Roll or Per Pallet Pricing.

# Q U O T A T I O N

JOB NAME: **Sample Job**

Date....: 00/00/0000

Quote #: **L-00000**

---

**\*\*\*SPECIAL NOTES\*\*\***

THIS QUOTE IS SUBJECT TO THE TERMS & CONDITIONS OF **LARKIN INDUSTRIES, INC.**  
COPIES OF DISCLAIMERS AND RECOMMENDATIONS MAY BE OBTAINED UPON REQUEST.  
THIS QUOTE IS VALID FOR 30 DAYS FROM ABOVE DATE.

\*THE ANSUL SYSTEM INCLUDES: PRE-PIPED HOOD(S), NOZZLES, DETECTION, MICRO SWITCH, PULL STATION, PERMIT (NOT TO EXCEED \$200.00), AIR TEST, FINAL HOOK-UP AND CERTIFICATION.

\*NOT INCLUDED IN PRICE AND CUSTOMER RESPONSIBLE FOR: UNION LABOR, DUMP TEST, GAS VALVE INSTALLATION, WIRING OF ELECTRICAL SHUT-DOWN, PREVAILING WAGES, HAND HELD FIRE EXTINGUISHER, FIRE ALARM HORN, ADDITIONAL LABOR CHARGES AS A RESULT OF COOKING EQUIPMENT LAYOUT CHANGES AFTER RELEASE OF ORDER OR ADDITIONAL TRIPS BY FIRE SYSTEM DISTRIBUTOR CAUSED BY JOBSITE DELAYS (HOOD, DUCT AND EQUIPMENT INSTALLATION NOT COMPLETE).

\*NOTE: IF RECESSED PULL STATION IS REQUIRED, INSTALLATION OF BOX AND CONDUIT SHALL BE PROVIDED BY OTHERS.

THANK YOU FOR THE OPPORTUNITY TO QUOTE YOU ON THE ABOVE KITCHEN VENTILATION PRODUCTS. IF YOU HAVE ANY QUESTIONS CONCERNING THE PRODUCTS OR PRICES QUOTED PLEASE CALL **THE LARKIN SALES TEAM AT (800) 322-4036.**